

**U. S. DEPARTMENT OF ENERGY
OFFICE OF CIVILIAN RADIOACTIVE WASTE MANAGEMENT**

**NUCLEAR WASTE TECHNICAL REVIEW BOARD
ENGINEERED BARRIER SYSTEM, TRANSPORTATION AND SYSTEMS
JOINT PANEL MEETING**

**SUBJECT: MULTI-PURPOSE CANISTER
SYSTEM DEVELOPMENT AND
PLANNING**


PRESENTER: RONALD A. MILNER

**PRESENTER'S TITLE
AND ORGANIZATION: Associate Director, Office of Storage and
Transportation.**


**PRESENTER'S
TELEPHONE NUMBER: (202) 586-9694**

**Dallas, Texas
November 1-2, 1993**

System Operational Concept with Multi-Purpose Canisters



Multi-Purpose Canister (MPC) System



MPC Conceptual Design Basis

- **Meet the requirements of:**
 - 10 CFR 71 Packaging and Transportation of Radioactive Material**
 - 10 CFR 72 Licensing Requirements for the Independent Storage of Spent Nuclear Fuel and High-Level Radioactive Waste**
- **Be compatible with the requirements of:**
 - 10 CFR 60 Disposal of High-Level Radioactive Waste in Geologic Repositories**
- **Incorporate utility requirements**
- **Openly review MPC concept with all stakeholders**

Waste Acceptance Requirements for MPC Conceptual Design

- **Initial requirements**
 - Maximize amount of SNF per canister
- **Constraint**
 - SNF has different physical, nuclear, and thermal characteristics

Design basis SNF characteristics:	<u>PWR</u>	<u>BWR</u>
— Maximum length (in)	180	180
— Maximum width (in)	9	6
— Maximum weight (lbs)	1720	730
— Burnup (MWd/MTU)	40,000	40,000
— Enrichment (wt% U-235)	3.75	3.75
— Decay (yrs)	10	10
— Decay Heat (kW/assembly)	0.675	0.317

Utility Requirements for MPC Conceptual Design

- **Initial requirements**
 - Maximize number of utilities
 - Suitable for on-site dry storage
- **Constraints**
 - Transportation mode
 - « Rail compatible 102 facilities
 - « Truck compatible 19 facilities
 - Handling capability if rail compatible (cask weight)
 - « >125 tons 56 facilities
 - « 100-125 tons 32 facilities
 - « 75-100 tons 14 facilities
 - ALARA
- **Design basis**
 - 125 ton cask 88 facilities
(32 with MPC transfer cask)
 - 75 ton cask 14 facilities
 - Truck cask 19 facilities
 - Welded closure
 - 9 foot diameter
 - Utility Transfer System

Transportation Requirements for MPC Conceptual Design

- **Initial requirements**
 - Maximize use of rail facilities
 - Minimize number of shipments
 - 10 CFR 71
 - « Dose rate: surface <200 mrem/hr,
at 2 meters <10 mrem/hr
- **Constraints**
 - Operate rail cars in unrestricted interchange (maximum width 128 in., maximum car weight 394,500 lbs.)
 - Cask exterior surface temperature: $<82^{\circ}\text{C}$
 - Criticality control: $k_{\text{eff}} <0.95$
 - Peak cladding temperature: 10-year-old SNF $<340^{\circ}\text{C}$,
5-year-old SNF $<380^{\circ}\text{C}$
 - Transportation overpack compatible with MPC
- **Design basis**
 - 125 ton maximum
 - Transportation accident requirements
 - « Burnup credit for criticality control
 - « Flooded conditions for criticality control
 - « No containment credit for MPC shell

Interim Storage Requirements for MPC Conceptual Design

- **Initial requirements**
 - Service life of 100 years
 - Transportable after long-term storage
 - 10 CFR 72
- **Constraints**
 - Criticality control: $k_{\text{eff}} < 0.95$
 - Peak cladding temperatures: 10-year-old SNF $< 340^{\circ}\text{C}$,
5-year-old SNF $< 380^{\circ}\text{C}$
 - Storage overpack/interim storage facility at utilities compatible with MPC
- **Design basis**
 - Containment credit for MPC
 - No internal inspection prior to transportation after storage

Disposal Requirements for MPC Conceptual Design

- **Initial requirements**
 - **MPC compatible with baseline thermal loading approach**
 - « **Waste package exterior temperature: $>100^{\circ}\text{C}$**
 - « **Near field temperature: $>100^{\circ}\text{C}$**
 - « **Areal loading: 30 - 114 kW per acre**
 - **MPC compatible with requirements of 10 CFR 60**
 - « **Criticality control: subcritical by five percent margin in k_{eff} , after uncertainties**
- **Constraints**
 - **Peak cladding temperature: $<350^{\circ}\text{C}$**
- **Design basis**
 - **Overpack is primary engineered barrier**
 - **Credit will be taken for all elements, as appropriate, including fuel cladding, MPC shell**
 - **Burnup credit for criticality control**

Key Trades

Issue	Alternatives	Rationale
Storage		
<ul style="list-style-type: none"> MPC closure mechanism 	Welded, Bolted	Minimize storage monitoring; crevice corrosion concern
Economics		
<ul style="list-style-type: none"> MPC shell material 	Stainless Steel, Carbon Steel, Alloy 825	Cost; transportability after long-term storage
<ul style="list-style-type: none"> Large MPC capacity 	24 PWR vs. 21PWR	Thermal constraint on cladding in repository (under review)
Criticality and Thermal		
<ul style="list-style-type: none"> Filler material 	Yes, No, Maybe Loading, Emplacement	Firm requirement not established
<ul style="list-style-type: none"> Burnup credit for large PWR MPC 	21 PWR capacity with, 17 PWR capacity without	Cost, shipment reduction
<ul style="list-style-type: none"> Basket neutron absorber lifetime, physical integrity 	Borated aluminum, Borated stainless steel	Heat transfer; lifetime at least equal to canister (under review)

RD&D Strategy for Unresolved Issues

- **Criticality Control**
 - Topical report working group being formed
 - Will brief NRC on long-term criticality evaluation needs 11/30/93
 - Topical report presentation planned early '95


- **Thermal Loading**
 - MGDS thermal loading study FY 93-94
 - Follow-on system studies FY 94-01
 - Large heater block tests FY 94-95
 - Abbreviated heater tests FY 96-99
 - ESF heater tests FY 96-01
 - Anticipated decision time frame FY 97-99

- **Burnup Credit**
 - Management meeting 8/27/93
 - First technical exchange 11/30-12/1/93
 - Three topical reports planned
 - « For storage and transport PWR SNF - submitted 9/94
 - « For disposal PWR/BWR SNF - submitted 9/95
 - « For storage and transport BWR SNF - if needed
 - One year NRC turnaround requested

Conceptual Designs for MPC


Size	Capacity	Reactors Served	Number of Assemblies
• 125 Ton MPC	21 PWR	64	109,000
	40 BWR	24	112,000
• 75 Ton MPC	12 PWR	5	8,000
	24 BWR	9	33,000
• Remainder of projected 298,000 SNF assemblies would be picked up from reactors in truck casks.			

125 - Ton 21 PWR Configuration



PC0687

75 - Ton 12 PWR Configuration



Contingencies

- **MPC Not Emplaceable**
 - **Cause:**
 - « **Incompatible with repository requirements, including criticality control and thermal loading**
 - **Impact:**
 - « **Additional cost to open, then rework, redesign and dispose, or convert to dual purpose MPC system**
 - « **Dual purpose MPC is upper bound of impact, could add up to \$500 million to program cost**

- **MPC Not Transportable After Long-Term Storage**
 - **Cause:**
 - « **Uncertainty over condition of basket and contents**
 - **Impact:**
 - « **Additional cost to open, then rework or design and dispose**
 - « **Could add up to \$500 million to program cost**

- **No MRS**
 - **Cause:**
 - « **Failure to obtain MRS site consistent with system requirements**
 - **Impact:**
 - « **Increased at-reactor dry storage, increased system costs**
 - « **MPC mitigates impact**

MPC Conceptual Design Report Products

- **Volume I Summary Report**
- **Volume II Conceptual Designs**
 - **MPC**
 - **Transportation Cask**
 - **MRS**
 - **Utility Transfer System**
- **Volume III Draft RFP and Design Specifications
(Procurement Sensitive)**
- **Volume IV Cost and Schedule**
- **Volume V Supporting Studies
(Concept of Operations, Repository and
Regulatory Considerations, others)**
- **Other related products
(Life Cycle Cost, Risks and Contingencies, Health and
Safety, Alternative Cask/Canister Concepts)**

Factors for Decision to Proceed with MPC


- **Should DOE incorporate an MPC system into the baseline and commence design?**
- **Primary criteria - evaluated for nominal case and contingencies**
 - **Health and safety**
 - **Life cycle cost**
 - **Licensing and regulatory compliance**
 - **Stakeholder acceptance**
 - **Waste acceptance schedule**
 - **Standard contract impacts**
 - **Flexibility in overall waste system**
- **Inputs to decision process**
 - **Conceptual Design Report**
 - **IMRG review**
 - **EI review**
 - **Stakeholder workshop**
 - **Environmental input**
 - **NRC**
 - **NWTRB**

MPC System Schedule

- **MPC Schedule**
 - **Decision on proceeding with MPC change to technical cost/schedule baseline - January '94**
 - **Issue RFPs for MPC design contracts - April '94**
 - **Award MPC design contracts - December '94**
 - **MPC Safety Analysis Report Design completed for License Application submission to NRC - December '95**
 - **Complete final Environmental Assessment for MPCs - December '95**
 - **MPC system prototype testing complete - March '97**
 - **NRC issue Certificate of Compliance for MPCs under 10CFR71 and 10CFR72 - June '97**
 - **Issue RFPs for MPC fabrication - September '96**
 - **Award MPC fabrication contracts - June '97**
 - **Start MPC deployment - January '98**
 - **Waste Package License Application Design activities - start June '96; completed 2001**

MRS MSA PROJECT MASTER SCHEDULE

TESS 10/21
MPC_10/21.dwg



MPC Conceptual Design Conclusions

- **Report asserts MPC approach offers advantages**
 - **Initial investment that should reduce national cost**
 - **Provides flexibility in interim storage system**
 - **Facilitates system standardization**
 - **Reduces bare SNF handlings**
- **MPC contingencies need to be addressed through**
 - **Analysis**
 - **Research**
 - **Design**
- **Decision making approach must encompass**
 - **Regulatory**
 - **Programmatic**
 - **Technical**
 - **Stakeholder**