

**U.S. DEPARTMENT OF ENERGY
OFFICE OF CIVILIAN RADIOACTIVE WASTE MANAGEMENT**

**NUCLEAR WASTE TECHNICAL REVIEW BOARD
FULL BOARD MEETING**

**SUBJECT: FUTURE TESTING IN THE
EXPLORATORY STUDIES FACILITY**

PRESENTER: NED Z. ELKINS

**PRESENTER'S TITLE
AND ORGANIZATION: DEPUTY TECHNICAL PROJECT OFFICER
LOS ALAMOS NATIONAL LABORATORY
LAS VEGAS, NEVADA**

**PRESENTER'S
TELEPHONE NUMBER: (702) 794-7097**

**LAS VEGAS, NEVADA
OCTOBER 19-20, 1993**

Near-term Exploratory Studies Facilities (ESF) Milestones Important to ESF Testing

Construction of Alcove 1	Ongoing
Initial Hydrologic Testing	October '93 - June '94
Start of TBM Excavation	August '94
Entry into block at TSw2 Horizon	March '95
TBM Daylight (South Ramp)	May '96
Initial Construction of Core Test Area (CTA) (MTL)	June '96

Detailed Test Planning

- **Planning sequence generally follows implementation sequence**
- **Elements of detailed Planning:**
 - **Test and facility design requirements**
 - **Test performance criteria**
 - **Interference and site performance impact analyses**
 - **Procedures development**
 - **Procurement planning**
 - **Schedules, integrated networks, cost estimation**
- **Emphasis on flexibility and data management**

Tests Planned in ESF Ramps and Drifts

Geologic/geohydrologic tests

- **Underground geologic mapping**
 - **Consolidated sampling**
 - **Intact-fractures**
 - **Percolation***
 - **Radial boreholes***
 - **Hydrochemistry***
 - **Hydrologic properties of major faults***
 - **Diffusion***
 - **Tomography/VSP**
 - **Perched water**
- * Tests requiring alcoves

Tests Planned in ESF Ramps and Drifts

(Continued)

Geomechanical and engineering tests

- Consolidated sampling
- Excavation effects*
- Demonstration breakout room (TSw1 heater test)*
- Plate loading*
- Excavation investigations (convergence, monitoring, stability, ventilation)
- Overcore stress*
- *In situ* seal components testing*

* Tests requiring alcoves

Tests Planned for Main Test Level (MTL) Core Test Area (CTA)

Thermal and Waste Package Environment Tests

The CTA will support a consolidated program of tests meeting the information needs of the following activities:

- Consolidated sampling**
- Canister-scale heater test**
- Heated block**
- Thermal stress**
- Heated room**
- Repository horizon near-field hydrologic environment**
- Geomechanical attributes of the waste package environment**

Tests Planned for Main Test Level (MTL) Core Test Area (CTA)

(Continued)

Geologic/Geohydrologic Tests

- **Underground geologic mapping**
- **Consolidated sampling**
- **Percolation**
- **Radial boreholes**
- **Diffusion**
- **Hydrochemistry**
- **Tomography/VSP**

Geomechanical and Engineering Tests

- **Consolidated sampling**
- **Plate loading**
- **Rock mass strength**
- **Sequential drift mining**
- **Excavation investigations (convergence, monitoring, stability, ventilation)**
- **Overcore stress**

ESF Construction Phase (Non-Deferrable) Tests

North Ramp Pad Area Construction

- **Geological mapping of surface exposures**

North Ramp Starter Tunnel

- **Geologic mapping (drill/blast)**
- **Limited consolidated sampling**
 - **Mineralogy/petrology**
 - **Chloride/Chlorine-36**
 - **Matrix hydrologic properties**
- **Perched water (contingency)**
- **Construction monitoring/design verification**

ESF Construction Phase (Non-Deferrable) Tests

(Continued)

North Ramp and TSw2 Main Drift (TBM Excavation)

- **Geologic mapping**
- **Consolidated sampling**
- **Perched water (contingency)**
- **Construction monitoring/design verification**
- **Radial boreholes (anisotropy and contact)**
- **Hydrochemistry**
- **Hydrologic properties of major faults (initial geothermal phase)**


ESF Test Program Consolidation

Groups of tests are being consolidated, where feasible, to minimize construction impact and to streamline data acquisition

Areas of consolidation

- 1. Nine ESF sampling activities combined into a “consolidated sampling program” supported in the field by the underground geologic mapping activity**
- 2. Six thermal/waste package environment activities consolidated into a single test program with initial and long-term (confirmation) phases**
- 3. Excavation effects and sequential drift mining tests combined as a single test program performed in conjunction with drift development for large-scale thermal/waste package environment testing**
- 4. Consolidation of bulk permeability tests and radial borehole tests into single test program with common methodology**
- 5. Consolidation of five excavation monitoring test activities into single program integrated with construction program and supported by construction contractors**

North Ramp and TBM Setup - Profile View



LEGEND

FAULT ZONE

RAMP CONFIGURATION

EXISTING GROUND

COMMENT

NORTH PORTAL CUT INTO FAULT AT ST. 0+00

ALSO, IS APPROXIMATELY LOCATED AT ST. 1+40

TWO THOUSAND FEET GRID LENGTH COORDINATES ARE BASED ON THE NEVADA STATE COORDINATE SYSTEM CENTRAL ZONE

DIMENSIONS AND ELEVATIONS ARE SHOWN IN FEET. FEET ARE ROUNDED TO ZERO DECIMAL PLACES. WHERE DIFFERENT BOUNDARY ELEVATIONS AND READINGS OCCUR DUE TO SURFACE ELEVATIONS WILL VARY.

STARTED TUNNEL CONFIGURATION AND AZIMUTH FOR THE FIRST 200 FEET (60 M) IS BASED ON TITLE II PACKAGE DESIGN DRAWING.

TEMPORARILY PROVISIONAL ANGLE ESTIMATION FROM SURFACE SURVEY TAKEN AT RAMP CENTER LINE

FAULT TRACE INFORMATION EXCEPT FOR THE BOW RIDGE FAULT ARE DERIVED FROM A 100-FOOT DEPTH PROBE RECORD OF DISCONTINUITIES FROM U.S. OPEN FILE REPORT NO. 434. PRELIMINARY GEOLGIC MAP AND SECTION BY TOTT AND BURN. THE BOW RIDGE FAULT TRACE IS SHOWN AT NORTH END IS BASED ON PRELIMINARY FIELD WORK FROM LOGS, CORE AND SOIL TEST ELEVATIONS.

TBM CONFIGURATION

A - CUTTER HEAD

CAR # FUNCTION CONTENTS

- 1 TRANSFORMER, SPARE CUTTER PLATE
- 2 LUNCH ROOM, TOILET, FIRST AID ROOM
- 3 CHOP AREA

B - MAPPING PLATFORM ON TRAILING FLOOR SECTION

- 4 CABLE STORAGE, BENTLINE CARTRIDGE, CONVEYER TAIL PIECE, CABLE AND MISCELLANEOUS STORAGE

ESTIMATED TOTAL LENGTH = 450 FT

Best Available Copy