

**U.S. DEPARTMENT OF ENERGY  
OFFICE OF CIVILIAN RADIOACTIVE WASTE MANAGEMENT**

**NUCLEAR WASTE TECHNICAL REVIEW BOARD  
FULL BOARD MEETING**

**SUBJECT: DRILLING PROGRAM UPDATE**

**PRESENTER: DENNIS R. WILLIAMS**

**PRESENTER'S TITLE CHIEF, SITE INVESTIGATIONS BRANCH  
AND ORGANIZATION: DEPARTMENT OF ENERGY  
YUCCA MOUNTAIN SITE CHARACTERIZATION PROJECT  
LAS VEGAS, NEVADA**

**PRESENTER'S  
TELEPHONE NUMBER: (702) 794-7968**

**LAS VEGAS, NEVADA  
OCTOBER 19-20, 1993**

# **Drilling Program**

**More appropriately...**

**"Borehole Sampling, Testing, and  
Monitoring Program"**

# **This Presentation is About Myths, Facts, and Data**

**We will**

- **Eliminate the myths**
- **State the facts**
- **Present and discuss the data**

# Myth

- **This is a drilling program**

# Fact

- **This is a testing-and-sampling program using a testing-and-sampling system**
- **We are not drilling Yucca Mountain; we are testing and sampling Yucca Mountain**

# Myth

- **The LM-300 is an inefficient drilling platform**

# Myth

- **The LM-300 is an expensive drill rig to acquire and operate**

# **Fact**

- **The LM-300 is an expensive testing-and-sampling system to acquire and operate**

**However, the LM-300 "rig" cost is commensurate with its size and complexity**



# Overview

- **Sampling-and-testing objectives**
- **LM-300 as a sampling-and-testing system**
- **YMP drilling development history**
- **Drilling progress from recent experience**
- **Research and development emphasis in FY94**
- **System utilization**
- **Geophysical logging**
- **FY94 drill, test, complete and monitor schedule**
- **Long term**
- **Specific questions/comments**

# Overview

- **Sampling-and-testing objectives**
- **LM-300 as a sampling-and-testing system**
- **YMP drilling development history**
- **Drilling progress from recent experience**
- **Research and development emphasis in FY94**
- **System utilization**
- **Geophysical logging**
- **FY94 drill, test, complete and monitor schedule**
- **Long term**
- **Specific questions/comments**

# Sampling and Testing Objectives


- Obtain core containing the *in situ* conditions of the mountain
- Provide boreholes without disturbing the *in situ* conditions of the mountain

# Clean versus Dirty Borehole


- **Testing cannot detect contamination in fractures**
- **No basis for evaluating the impact to the borehole wall for gas-phase testing, if the system functions improperly**

# Overview


- **Sampling-and-testing objectives**
- **LM-300 as a sampling-and-testing system**
- **YMP drilling development history**
- **Drilling progress from recent experience**
- **Research and development emphasis in FY94**
- **System utilization**
- **Geophysical logging**
- **FY94 drill, test, complete and monitor schedule**
- **Long term**
- **Specific questions/comments**







# LM-300 SAMPLING SYSTEM AT UZ-14





# Overview

- **Sampling-and-testing objectives**
- **LM-300 as a sampling-and-testing system**
- **YMP drilling development history**
- **Drilling progress from recent experience**
- **Research and development emphasis in FY94**
- **System utilization**
- **Geophysical logging**
- **FY94 drill, test, complete and monitor schedule**
- **Long term**
- **Specific questions/comments**

# YMP Drilling Development History

## Development

- **Prototype development of dual-wall system**
  - 1989-1991; \$6 MM
  - Established feasibility of dual-wall system for unsaturated zone
- **LM-300 system acquisition and shakedown**
  - 1992; \$6 MM
  - Established dual-wall (unsaturated zone sampling) capability at YMP

## Enhancement

- **Bit-testing program (ongoing)**

# YMP Drilling Studies History


- **Bit-testing program**
  - **1991; \$221K**
    - Compared Apache Leap with Yucca Mountain tuff
    - Initiated bit development program (BDP)
  - **1992; \$397K**
    - BDP resulted in improved PDC bits and increased drill-bit industry interest in YMP (e.g., Hughes Tool Co.)
    - Initiated Vibratory Core Rod Simulation (VCRS) Study
  - **1993; \$500K**
    - VCRS defined critical rotary speeds for core rods
    - Developed VCRS program for field use
    - Continued BDP with adaptation of INTEQ Data Acquisition system to improve VCRS model

# Overview

- **Sampling-and-testing objectives**
- **LM-300 as a sampling-and-testing system**
- **YMP drilling development history**
- **Drilling progress from recent experience**
- **Research and development emphasis in FY94**
- **System utilization**
- **Geophysical logging**
- **FY94 drill, test, complete and monitor schedule**
- **Long term**
- **Specific questions/comments**


# UE-25 UZ-16 Versus USW UZ-14

## Drill Rig = LM-300



**UE-25 UZ-16**

186 Shifts Total Rig Time  
 Total Footage = 1,686 Ft  
 Ft/8 Hr Shift = 9.1 Ft/Shift  
 Ft/Hr = 1.13 Ft/Hr




**USW UZ-14**


69 Shifts Total Rig Time  
 Total Footage = 1,182 Ft  
 Ft/8 Hr Shift = 17.1 Ft/Shift  
 Ft/Hr = 2.14 Ft/Hr

**UZ-16 includes drilling through March 16, 1993 (Total Depth)**  
**UZ-14 includes drilling through July 26, 1993 (1,182 Ft.)**

# UE-25 UZ-16 Performance



# USW UZ-14 Performance



# **UZ-14 Cementing Perched Water Zone (Phase 1, 1255-1271 ft)**

- **Open-hole cementing reduced water inflow from 60+ gallons/hour to "0" gallon/hour on first attempt**
- **Halliburton "Micro Matrix" slurry found to be effective for small fracture cementing**
- **Cementing design effective for satisfying test interference controls**



## **UZ-14 Cementing Perched Water Zone (Phase 2, 1275-1276 ft)**

- **Open-hole cementing reduced water inflow from 3+ gallons/hour to "0" gallon/hour on first attempt**
- **Halliburton "Micro Matrix" slurry found to be effective for extremely small perched-water inflow**
- **Cementing design even more simplified than Phase 1**

# FY92-94 Programs

<u>Program</u>	<b>FY92</b>		<b>FY93</b>		<b>FY94</b>	
	<u>Ft.(Holes)</u>	<u>Direct \$</u>	<u>Ft.(Holes)</u>	<u>Direct \$</u>	<u>Ft.(Holes)</u>	<u>Direct \$</u>
UZ	800 (1)	\$635K	2170 (2)	\$1591K	1718 (2)	\$750K
SD					3800 (2)	\$1500K
UZN	2242 (16)	\$621K	980 (8)	\$247K		
RAMP	150 (1)	\$36K	4398 (7)	\$1060K	2425 (5)	\$450K
<b>Total =</b>	<b>3,192 Ft.</b>	<b>\$1,292K</b>	<b>7,548 Ft.</b>	<b>\$2,898K</b>	<b>7,943 Ft.</b>	<b>\$2,700K</b>

**Drill Rigs**  
**CME 550**  
**CME 850**  
**Joy-1**  
**Failing 1500**  
**LM-300**

**Testing, completion, and  
monitoring, FY94:**  
**Rig months=5.4; direct=\$500K**

# Overview

- **Sampling-and-testing objectives**
- **LM-300 as a sampling-and-testing system**
- **YMP drilling development history**
- **Drilling progress from recent experience**
- **Research and development emphasis in FY94**
- **System utilization**
- **Geophysical logging**
- **FY94 drill, test, complete and monitor schedule**
- **Long term**
- **Specific questions/comments**


# **Technology Studies Emphasis FY94**

- 1. Venturi Feasibility**
- 2. Vibration Analysis Program**
- 3. Deviation Control Simulator**
- 4. Finish Core-Bit Testing Report**

# Venturi Feasibility

- **Determine feasibility of generating vacuum downhole at reaming bit**
- **Rough prototype worked with limited success in early prototype drilling program**
- **Could be essential to provide "balanced air" drilling beyond 2000 ft.**
- **Not readily available, if needed**

# CSM Core Rod Vibration Study (VCRS Program)




Drilling Eng. Research Group  
Prof. Mitchell et.al.


- Shows critical rotary speeds for core rod
- Graphical presentation of "high risk" rotary speeds
- Provides previously unavailable analysis of CHD-101 coring system in dry coring environment

# Coring Deviation Control

**THE  
P  
R  
O  
B  
L  
E  
M**




# Core Bit Performance Comparison (60 RPM)





# Core Bit Performance

## Bit Type vs Penetration Rate




Impregnated Diamond Carbonado PDC

\* UZ-14 data through 8/4/93 only

# Core Bit Performance


## Bit Type versus Footage Drilled



■ Impregnated Diamond   ■ Carbonado   ▨ PDC

\* UZ-14 data through 8/4/93 only

# UZ-14 versus UZ-16 Average Percent Recovery for Common Rock Units




# Overview

- **Sampling-and-testing objectives**
- **LM-300 as a sampling-and-testing system**
- **YMP drilling development history**
- **Drilling progress from recent experience**
- **Research and development emphasis in FY94**
- **System utilization**
- **Geophysical logging**
- **FY94 drill, test, complete and monitor schedule**
- **Long term**
- **Specific questions/comments**

**No Basis for Determining Efficiency**

**Utilization 21%**

**LM-300 Shift Alternatives  
(Typical 2080' Borehole @ 15 Ft./Shift)**



Includes Shutdown For All Normal Holidays & 2 Weeks At Christmas/New Year's

Shift Schedule	Shifts Per Week	Total Drilling Days	Total Drilling Shifts	Total Calendar Days	Total Available Shifts	Equipment Utilization
24 Hours/Day, 7 Days/Week (No Holidays)	21	46.2	138.7	46.2	138.7	100%
24 Hours/Day, 7 Days/Week	21	46.2	138.7	47.2	141.7	98%
24 Hours/Day, 5 Days/Week	15	46.2	138.7	69.2	207.7	67%
16 Hours/Day, 5 Days/Week	10	69.3	138.7	117.3	352.0	39%
8 Hours/Day, 5 Days/Week	5	138.7	138.7	215.7	647.0	21%

# Overview

- **Sampling-and-testing objectives**
- **LM-300 as a sampling-and-testing system**
- **YMP drilling development history**
- **Drilling progress from recent experience**
- **Research and development emphasis in FY94**
- **System utilization**
- **Geophysical logging**
- **FY94 drill, test, complete and monitor schedule**
- **Long term**
- **Specific questions/comments**

# **FY93 Geophysics Accomplishments at Yucca Mountain**

- **Geophysical Borehole Logging**
  - **UE-25 UZ-16 - Standard suite, seismic (Zero-offset) and VSP walkaway surveys, gravity and magnetics, neutron, prototype logs (RAAX, pulsed neutron, radar, geochemical), downhole video 7/22-8/12, 1993**
  - **USW NRG-6, UE-25 NRG-2 - slim-hole suite, seismic check-shot, Gyro, TV, (also, magnetics and VSP in NRG-6)**
  - **USW UZ-1 - Gyro survey (in preparation for drilling UZ-14 on same pad)**
  - **USW WT-2 - VSP profiling and zero-offset seismic, 8/23-8/25, 1993 (LBL)**
  - **Neutron logging on all N-holes and WT-2**
  - **Prototype crosshole seismic work at CSM in preparation for VSP in UZ-16**



# **FY93 Geophysics Accomplishments at Yucca Mountain**

(Continued)

- **Seismic Refraction**
  - **Windy Wash fault (SW of proposed repository area)**
- **Gravity and Magnetics**
  - **Yucca Wash area (North of proposed repository area)**
  - **Midway Valley (East of proposed repository area)**
- **Geodetic Leveling**
  - **Completed re-survey of level lines (base station network);  
re-surveyed GPS base stations**

# **FY93 Geophysics Accomplishments at Yucca Mountain**

(Continued)

- **Seismic Monitoring**
  - **Continuous 24-hour coverage in Southern Great Basin Seismic Monitoring Network**
  - **Seismic field experiment in Midway Valley (ground motion site response for ESF surface facilities design)**
  - **Mapping of precariously balanced rocks (from which is inferred past levels of ground-shaking)**
  - **Three new broad-band stations installed near Beatty to improve earthquake location parameters**
  - **Recording of non-proliferation experiment (NPE) on September 22, 1993, with numerous portable seismographs**
- **Engineering Geophysical Tests on Rock Samples**
  - **Determined for North Ramp core samples in surface facilities areas**

# **FY94 Planned Geophysics at Yucca Mountain**

(Continued)

- **Geophysical Borehole Logging**

- **UZ-14: 4- or 6-arm caliper, gravity, video, gyro, dual induction, sidewall neutron, NPLT; possibly dielectric log, magnetics, velocity check shot, neutron moisture, prototype logging 11/93-12/93**
- **UE-25 UZ-16: VSP reconnaissance survey with grouted-in 96-geophone string**
- **NRG-2, -2a, -2b, -3, -4, -5, -6, and -7: Resistivity, gamma, density, neutron, gyro, video, caliper 10/93-11/93**
- **WT-2: Resistivity, gamma, density, neutron, caliper, video, gyro deviation 10/93; also, heat flow**
- **WT- and G-holes: Heat-flow surveys in about 30 boreholes**
- **SD-12: Phased logging possible above and below WT; similar logs to those at UZ-14**

# **FY94 Planned Geophysics at Yucca Mountain**

(Continued)

- **Seismic Reflection**

- **Between WT-2 and UZ-16, in support of ESF main drift design (LBL)**
- **Possible NW-SE line through Drill Hole Wash, in support of ESF north ramp design (LBL)**
- **Possible survey along Yucca Crest Road, in support of faulting studies (LBL)**

- **Seismic Monitoring**

- **Continuous 24-hour coverage in Southern Great Basin seismic monitoring network**
- **Mapping of precariously balanced rocks (from which is inferred past levels of ground-shaking)**

# **FY94 Planned Geophysics at Yucca Mountain**

(Continued)


- **Geodetic Leveling**
  - **Analyses of leveling data collected in FY93**
- **Engineering Geophysical Tests on Rock Samples**
  - **Determined for North and South Ramp core samples, surface facilities areas (SNL)**
  - **Unspecified geophysical tests in the North Ramp and alcoves (LANL; LLNL); possibly to include laser-induced breakdown spectroscopy**

# **UZ-16 Lithology Compared to UZ-16 Geophysical Logs**

USW NRG6

AREA 25 NTS

29-JUN-1993



USW NRG6


AREA 25 NTS

29-JUN-1993

UE 25 UZ 16 (VSP 2)

AREA 25

AUGUST, 1993



YUCCA MOUNTAIN SITE CHARACTERIZATION PROJECT  
 TECHNICAL AND MANAGEMENT SUPPORT SERVICES  
 Drilling Support and Sample Management  
 INFORMATION COPY QA:N/A October 11, 1993

UE 25 UZ 16 (VSP 2)

AREA 25

AUGUST, 1993




# Overview

- **Sampling-and-testing objectives**
- **LM-300 as a sampling-and-testing system**
- **YMP drilling development history**
- **Drilling progress from recent experience**
- **Research and development emphasis in FY94**
- **System utilization**
- **Geophysical logging**
- **FY94 drill, test, complete and monitor schedule**
- **Long term**
- **Specific questions/comments**








14. 2/28/95  
 15. 3/1/95  
 16. 3/1/95  
 17. 3/1/95  
 18. 3/1/95  
 19. 3/1/95  
 20. 3/1/95  
 21. 3/1/95  
 22. 3/1/95  
 23. 3/1/95  
 24. 3/1/95  
 25. 3/1/95  
 26. 3/1/95  
 27. 3/1/95  
 28. 3/1/95  
 29. 3/1/95  
 30. 3/1/95  
 31. 3/1/95  
 32. 3/1/95  
 33. 3/1/95  
 34. 3/1/95  
 35. 3/1/95  
 36. 3/1/95  
 37. 3/1/95  
 38. 3/1/95  
 39. 3/1/95  
 40. 3/1/95  
 41. 3/1/95  
 42. 3/1/95  
 43. 3/1/95  
 44. 3/1/95  
 45. 3/1/95  
 46. 3/1/95  
 47. 3/1/95  
 48. 3/1/95  
 49. 3/1/95  
 50. 3/1/95  
 51. 3/1/95  
 52. 3/1/95  
 53. 3/1/95  
 54. 3/1/95  
 55. 3/1/95  
 56. 3/1/95  
 57. 3/1/95  
 58. 3/1/95  
 59. 3/1/95  
 60. 3/1/95  
 61. 3/1/95  
 62. 3/1/95  
 63. 3/1/95  
 64. 3/1/95  
 65. 3/1/95  
 66. 3/1/95  
 67. 3/1/95  
 68. 3/1/95  
 69. 3/1/95  
 70. 3/1/95  
 71. 3/1/95  
 72. 3/1/95  
 73. 3/1/95  
 74. 3/1/95  
 75. 3/1/95  
 76. 3/1/95  
 77. 3/1/95  
 78. 3/1/95  
 79. 3/1/95  
 80. 3/1/95  
 81. 3/1/95  
 82. 3/1/95  
 83. 3/1/95  
 84. 3/1/95  
 85. 3/1/95  
 86. 3/1/95  
 87. 3/1/95  
 88. 3/1/95  
 89. 3/1/95  
 90. 3/1/95  
 91. 3/1/95  
 92. 3/1/95  
 93. 3/1/95  
 94. 3/1/95  
 95. 3/1/95  
 96. 3/1/95  
 97. 3/1/95  
 98. 3/1/95  
 99. 3/1/95  
 100. 3/1/95

Revision 1  
 BAYTECH SERVICES NEVADA  
 NMP 8BT ACTIVITY SCHEDULE FY93-FY94  
 DRILL, TEST, COMPLETION & MONITORING  
 1. 3/1/95  
 2. 3/1/95  
 3. 3/1/95  
 4. 3/1/95  
 5. 3/1/95  
 6. 3/1/95  
 7. 3/1/95  
 8. 3/1/95  
 9. 3/1/95  
 10. 3/1/95  
 11. 3/1/95  
 12. 3/1/95  
 13. 3/1/95  
 14. 3/1/95  
 15. 3/1/95  
 16. 3/1/95  
 17. 3/1/95  
 18. 3/1/95  
 19. 3/1/95  
 20. 3/1/95  
 21. 3/1/95  
 22. 3/1/95  
 23. 3/1/95  
 24. 3/1/95  
 25. 3/1/95  
 26. 3/1/95  
 27. 3/1/95  
 28. 3/1/95  
 29. 3/1/95  
 30. 3/1/95  
 31. 3/1/95  
 32. 3/1/95  
 33. 3/1/95  
 34. 3/1/95  
 35. 3/1/95  
 36. 3/1/95  
 37. 3/1/95  
 38. 3/1/95  
 39. 3/1/95  
 40. 3/1/95  
 41. 3/1/95  
 42. 3/1/95  
 43. 3/1/95  
 44. 3/1/95  
 45. 3/1/95  
 46. 3/1/95  
 47. 3/1/95  
 48. 3/1/95  
 49. 3/1/95  
 50. 3/1/95  
 51. 3/1/95  
 52. 3/1/95  
 53. 3/1/95  
 54. 3/1/95  
 55. 3/1/95  
 56. 3/1/95  
 57. 3/1/95  
 58. 3/1/95  
 59. 3/1/95  
 60. 3/1/95  
 61. 3/1/95  
 62. 3/1/95  
 63. 3/1/95  
 64. 3/1/95  
 65. 3/1/95  
 66. 3/1/95  
 67. 3/1/95  
 68. 3/1/95  
 69. 3/1/95  
 70. 3/1/95  
 71. 3/1/95  
 72. 3/1/95  
 73. 3/1/95  
 74. 3/1/95  
 75. 3/1/95  
 76. 3/1/95  
 77. 3/1/95  
 78. 3/1/95  
 79. 3/1/95  
 80. 3/1/95  
 81. 3/1/95  
 82. 3/1/95  
 83. 3/1/95  
 84. 3/1/95  
 85. 3/1/95  
 86. 3/1/95  
 87. 3/1/95  
 88. 3/1/95  
 89. 3/1/95  
 90. 3/1/95  
 91. 3/1/95  
 92. 3/1/95  
 93. 3/1/95  
 94. 3/1/95  
 95. 3/1/95  
 96. 3/1/95  
 97. 3/1/95  
 98. 3/1/95  
 99. 3/1/95  
 100. 3/1/95



Revision 1


BATHOON SERVICES NEWADA  
 WY-01 ACTIVITY SCHEDULE FY83-FY84  
 WELL TEST, COMPLETION & MONITORING

# Overview

- **Sampling-and-testing objectives**
- **LM-300 as a sampling-and-testing system**
- **YMP drilling development history**
- **Drilling progress from recent experience**
- **Research and development emphasis in FY94**
- **System utilization**
- **Geophysical logging**
- **FY94 drill, test, complete and monitor schedule**
- **Long term**
- **Specific questions/comments**

# LM-300 Schedule for 40 Deep Boreholes (SCP Plan)

(Based on UZ-14 Performance)



\* Basis

- 40 Deep holes @ 2,500 ft/hole = 100,000 ft core for program
- 1 crew can drill out 3,500 ft core/year assuming 250 working days, 5 days/week, 50 weeks at 14 ft/crew.

**WBS Elements**

- (1) 1.2.3.5 Drilling
- (2) 1.2.3 Site Investigation
- (3) 1.2.7.3 FOC
  - 1.2.13.2 Safety & Health
  - 1.2.15.2 Administrative Support
- (4) 1.2.7.8 NTS
  - 1.2.9.2 Project Control
  - 1.2.13.3 Environmental Compliance
  - 1.2.15.3 Training

**Assumptions**

- A. Incremental Crew Cost Increases as a result of Weekend Rates
- B. Includes \$250K/Yr/Crew for drilling consumables
- C. Reflects increases due to concurrent work required with second LM-300
- D. Includes 10,000K 1 time capital cost for additional LM-300

# Overview

- **Sampling-and-testing objectives**
- **LM-300 as a sampling-and-testing system**
- **YMP drilling development history**
- **Drilling progress from recent experience**
- **Research and development emphasis in FY94**
- **System utilization**
- **Geophysical logging**
- **FY94 drill, test, complete and monitor schedule**
- **Long term**
- **Specific questions/comments**



# **Specific Question/Comment #1**

## **Large Diameter Holes versus Small Diameter Holes**

### **Considerations**

- **Preservation of *in situ* borehole wall conditions**
  - **Dual-wall reverse circulation in larger diameter holes**
- **Larger diameter holes required for borehole instrumentation packages**
- **Small-diameter holes are being used, where feasible**

# **Specific Question/Comment #2**

## **Drilling/Testing Decision-Making Process**

- **Work-Scope Consolidation**
  - **SD-12 and MDG-2 requirements combined in one borehole**
- **Borehole catalog incorporates results of drilling-consolidation workshop**
- **Organizations: DOE, M&O, and Participants**

## **Specific Question/Comment #3**

### **Intermittent versus Continuous Core**

- **Tremendous need for core samples, especially in early part of program**
- **Drilling-consolidation workshop documented in borehole catalog (total program core requirement reduced 30,000-38,000 ft = 25-30%)**
- **Experience in Topopah (i.e., NRG-5)**

# **Specific Question/Comment #4**

## **Needs for Dry-Drilled Core**

### **Considerations**

- **Study Plans 8.3.1.2.2.3 (Surface-Based)**  
**8.3.1.2.2.4 (ESF-Based)**

**Major unsaturated-zone study plans dry core and uncontaminated wall**

# **Specific Question/Comment #5**

## **Contracting Options**

- **REECo is the M&O for the DOE Nevada Test Site (YMP included) and is responsible for all drilling and construction**
- **For rapid ramp-up considerations, REECo can subcontract to fill drilling need, if they do not have an in-house capability**
  - **Provides capability for additional support for boreholes requiring LM-300-type drilling systems (most demanding requirements)**
  - **"Standard Drilling" requirements would be determined on an *ad hoc* basis (BIR 800 on JF-3)**

# **Specific Question/Comment #6**

## **Borehole Testing from Within ESF**

### **Considerations**

- **Size of openings 25' diameter, nominal**
- **Dry-drilling underground**
  - **Dust control**
  - **Ventilation system**
  - **All-electric power requirements**
- **Creation of direct pathways from repository level into primary barrier**

**10 CFR 60.15**

# **Specific Question/Comment #7**

## **New Core Tools Could Have Substantial Positive Impact on Core Production**

### **Considerations**

- **Increased coring rate from 7.39 to 21.4 ft/hr from UZ-16 to UZ-14, which led to nearly doubling the shift rate from 9 ft/shift to 17 ft/shift**
- **Faster penetration with aggressive bits (PDCs) puts greater vibration on coring string**
- **Faster penetration may lead to more fishing time (4% at UZ-16 versus 12% at UZ-14)**
- **Coring is 10% time component in UZ-14**

# **Specific Question/Comment #8**

## **Emphasize Testing in ESF versus SBT**

### **Considerations**

- **ESF is primarily directed to details of specific targets and to the lateral variability of key horizons, the proposed repository level, and the Calico Hills level**
- **SBT is a whole-block framework with emphasis on vertical and lateral spatial variability**