U.S. DEPARTMENT OF ENERGY OFFICE OF CIVILIAN RADIOACTIVE WASTE MANAGEMENT

NUCLEAR WASTE TECHNICAL REVIEW BOARD JOINT PANELS ON HYDROGEOLOGY & GEOCHEMISTRY AND STRUCTURAL GEOLOGY & GEOENGINEERING

SUBJECT: UNDERGROUND

TEST COORDINATION

PRESENTER:

WILLIAM J. BOYLE

PRESENTER'S TITLE

AND ORGANIZATION:

PHYSICAL SCIENTIST ASSISTANT MANAGER

FOR SCIENTIFIC PROGRAMS

YUCCA MOUNTAIN SITE CHARACTERIZATION PROJECT

LAS VEGAS, NEVADA

TELEPHONE NUMBER:

(702) 794-7595

WASHINGTON, D.C. NOVEMBER 17-18, 1994

- SCP test program was the basis for the Program Approach testing strategy
- DOE is in the process of further refining the Program Approach testing strategy

Underground Test Coordination

- Components
 - Pre-test Planning
 - Test Planning
 - Test Implementation
- Process
- Where & When

- 1. Project management approval of test program component with schedule requirements
- 2. Preliminary definition of each test component
- 3. Formal determination of facility design linkages and A/E notification
- 4a. Review and revision, as necessary, of test program baseline
- 4b. Initiation of study plan revisions incorporating approved program considerations (study plan approval required prior to field initiation)
- 5. Revision of ESFDR Appendix B requirements for each test component
- 6. Conceptual (preliminary) facility design (design package or revision) and procurement initiations or scheduling

1. Project management approval of thermal test program component (with schedule requirements)

- 2. Preliminary definition of each test component
 - Location (rock type, need for replication, orientation)
 - Configuration (spatial requirements, installation logistics)
 - Determination of major (high-level) facility requirements (utility estimates, construction/excavation requirements)
 - Preliminary constraint determinations (stand-off, zone of influence)

- 3. Formal determination of facility design linkages and A/E notification
 - Design Package(s) Inclusion
 - Timing of test support construction against ESF construction schedule
 - Initiation of design and construction planning

- 4a. Review and revision, as necessary, of test program baseline
- 4b. Initiation of study plan revisions incorporating approved program considerations (study plan approval required prior to field initiation)

- 5. Revision of ESFDR Appendix B requirements for each test component of consolidated components
 - Definition of TEST
 - Functional Requirements
 - Performance Criteria (Facility)
 - Constraints (High Level)
 - Interface Requirements
 - Assumptions

6. Conceptual (preliminary) facility design (design package or revision) and procurement initiations or scheduling

Thermal Program Test Planning Process

I. Development of Test Planning Packages

- Principal Investigator criteria for test components
- Finalization of facility requirements (A/E)
 - -- Alcove (spatial) requirements
 - -- Power and utility requirements
- Construction support definition (construction management)
- Other test support requirements (e.g. sample handling, data collection)
- Review and incorporation of other program requirements (regulatory flowdown, health/environmental/safety)
- Evaluation of test interference/waste isolation impacts
- Finalization of test and facility constraints based on test planning and analysis of potential impacts

II. Development of Job Packages


- Final determination of participant involvement and responsibilities (scope)
- Determination of test support and implementation schedule/sequence
- Inclusion of scoping estimates into PACS planning (all participants)
- Formal assignment of reporting requirements, hold points, close-out requirements

Test Implementation

- With input and approval of field testing participants and support organizations, an administrative work plan is developed which provides comprehensive field-level recommendations of implementation logistics (implementation steps, interactions, overall coordination). The work plan provides the administrative "recipe" for test implementation consistent with the requirements and constraints developed under the TPP and JP.
- The ESF test coordination office establishes field communications with construction management, test program management, and participant organizations prior to construction start
- Test construction, set-up, and test implementation are initiated upon closure of all prerequisites and determination of field readiness

ESF TEST PROGRAM IMPLEMENTATION

Facility Design Integration and Construction Support Planning for Non-Deferred Alcoves and Test Locations



LEGEND FAULT ZONE RAMP CONFIGURATION REFERENCE GRID BOREHOLE LOCATION ADMINISTRATIVE/ILLUSTRATIVE USE DNLY TO NORTH PORTAL DIP DIR: N80E DIP: 4.2 DEGREES CS 12+00 PLANNED EXCAVATION DATE: SEPT. '95 TSwi NDN-CALE NOTED LITHOPHYSAL 11/1 4/4 4 THERMAL E566000 /cs ₁₇₊₀₀ DIMENSIONS AND ELEVATIONS ARE SHOWN IN METERS. METERS ARE ROUNDED TO TWO DECIMAL PLACES. WHERE DISCREPANCIES BETWEEN ELEVATIONS AND GRADIENTS OCCUR DUE TO ROUNDING ELEVATIONS VILL GOVERN. TYO THOUSAND FEET GRID. ENGLISH COORDINATES ARE BASED ON THE NEVADA STATE COORDINATE SYSTEM, CENTRAL ZONE. ALCIDVE 81 APPRIXIMATELY LIXATED AT CS 0+60 G+407 NORTH RAMP X-SECTION 185 m DRIFT TO REACH TSW2 AT 2 DEGREES PLANNED EXCAVATION DATES AT STATIONS CS 12+00 AND CS 28+00 BASED ON FY 1995 CONSTRUCTION SCHEDULE AND 1996 PRELIMINARY PLANNING. TSW1
TSW2 DIPPING AT 4.2 DEGREES 20 m STRIKE, DIP, AND THERMOMECHANICAL CONTACT INFORMATION IS BASED ON SNL QA DRAWING # 88-60-09, V QAIA, ESF NORTH RAMP CROSS SECTION ALONG RAMP FROM 0+00 TO 28+00.38 m FIG. 1 CS 21+50 1 E564000 HIGH-LITHOPHYSAL CS 28+00 EXCAVATION PLANNED EXCAVATION 96 MAIN DRIFT TIP ENTERING TSw2 SEE FIG. 1 FOR PROFILE VIEW THIS EXAMPLE ASSUMES THE DRIFT IS IN THE DIRECTION OF THE DIP AND TANGENT TO THE NORTH RAMP. ANY DIHER DIRECTION INCREASES THE LENGTH OF THE DRIFT. E562000 GRAPHIC SCALE IF THE SLOPE OF THE DRIFT INCREASED FROM 2 DEGREES TO 10 DEGREES, ITS LENGTH BECOMES 72 m TO REACH THE TOP OF TSW2. 975.36 m (3200 FT.)