


License Application Plan Viability Assessment - Volume 4

Presented to:
Nuclear Waste Technical Review Board

Presented by:
Carol L. Hanlon
Department of Energy



U.S. Department of Energy
Office of Civilian Radioactive
Waste Management

January 26-27, 1999

Purpose of the License Application Plan

(Civilian Radioactive Waste Management Program Plan)

- To identify remaining scientific investigations and engineering information needed to complete the License Application**
- To identify costs associated with securing this information**

LONG-TERM GOAL

- To submit a docketable License Application to the Nuclear Regulatory Commission**

Considerations

- **Opportunity to assess adequacy of revised approach to site characterization and design**
- **Draw on available models and data describing the natural system, repository, and waste package design**
- **Draw on Total System Performance Assessment**
- **Draw on strategy for evaluating waste containment and isolation (Repository Safety Strategy)**
- **Performance confirmation program continuing during construction and operation to further reduce performance uncertainties**

Intended Use of the License Application Plan

- Provide understanding of how DOE has identified, prioritized, and described major areas of remaining work to be conducted during next 4 years**
- Discuss statutory and regulatory activities**
- Discuss supporting work**
- Present schedule, costs for work identified**


- Goal: ability to produce a docketable license application**

License Application Plan NOT Intended to:

- **Provide lower-level detail on work activities identified**
 - Detailed information on work activities will be provided in Annual Plans and Multi-Year Planning System
 - Work plans and procedures will be identified in individual work packages available in the record system
- **Provide detail on statutory, regulatory, and support activities such as Quality Assurance Program, preparation of Site Recommendation, and License Application**
 - Details provided in separate management documents specific to each area, i.e., License Application Management Plan, and Quality Assurance Requirement Description

License Application Plan Organization


Volume 4



Areas of Emphasis

- **Rationale for Technical Work Needed to Complete the Postclosure Safety Case**
- **Postclosure Safety Case**
- **Expected Postclosure Performance**
- **Principal Factors of Postclosure Performance**
- **Technical Work Plans**

License Application Plan Rationale



Prioritization of Principal Factors

- **19 principal factors were prioritized to identify technical work with best potential to reduce uncertainty in the postclosure safety case**
 - **Consideration to factors to which peak dose rate most sensitive**
 - **This work has consequently received priority funding and resource allocation**

Prioritization of Principal Factors

(Continued)

Prioritization Considerations:

- 1. Significance of uncertainty to TSPA; effect of uncertainties on peak dose rate calculation: H, M, L**
- 2. Current Confidence (1= Low; 7= High)**
 - Is current representation realistic**
 - Does current representation capture entire range of conditions important to performance**

Prioritization of Principal Factors

(Continued)

- 3. Confidence goal (1 = Low; 7 = High)**
 - Feasible to be accomplished in time for input to Site Recommendation and License Application**
 - Desirable in significance to TSPA and important to defensibility of technical basis**
- 4. Priority = confidence goal - current confidence**

Confidence Goal Assessments

RSS Attributes	Principal Factors	* Signif. of Uncertainty	Current Conf.	Conf. Goal
Limited water contacting waste packages	1. Precipitation and infiltration into the mountain	M	4	5
	2. Percolation to depth	M	3	5
	3. Seepage into drifts	H	2	5
	4A. Effects of heat/excavation on flow (mountain)	M _b	1	2
	4B. Effects of heat/excavation on flow (drift scale)	M _b	2	4
	5. Dripping onto waste package	M	2	4
Long waste package lifetime	6. Humidity and temperature at waste package	L _{b,c}	5	4
	7. Chemistry of water on waste package	M	3	5
	8. Integrity of outer carbon steel WP barrier	M _a	4	5
Low rates of release for radionuclides from breached waste packages	9. Integrity of inner corrosion-resistant WP barrier	H _{a,b}	3	6
	10. Seepage into waste package	M	3	3
	11. Integrity of spent fuel cladding	H _a	3	5
	12. Dissolution of spent fuel & glass waste forms	M _{b,c}	4	5
	13. Neptunium solubility	M _{b,c}	4	5
Concentration reduction transport from waste packages	14. Formation & transport of radionuclide-colloids	M _{b,c}	2	4
	15. Transport through and out of EBS	M _{b,c}	3	4
	16. Transport through unsaturated zone	H _a	2	5
	17. Flow and transport in saturated zone	M	2	3
	18. Dilution from pumping	M	5	5
	19. Biosphere transport and uptake	L	5	5

* Subscripts: "a" = 0 to 10 kyr, "b" = 10 to 100 kyr, and "c" = 100 kyr to 1 Myr (no subscript = 0 to 1 Myr)

Prioritization Results

RSS Attributes	Principal Factors ^A	Current Conf.	Conf. Goal	Priority
Limited water contacting waste packages	1. Precipitation and infiltration into the mountain	4	5	1
	2. Percolation to depth	3	5	2
	3. Seepage into drifts	2	5	3
	4A. Effects of heat/excavation on flow (mountain)	1	2	1
	4B. Effects of heat/excavation on flow (drift scale)	2	4	2
	5. Dripping onto waste package	2	4	2
Long waste package lifetime	6. Humidity and temperature at waste package	5	4	0 ^B
	7. Chemistry of water on waste package	3	5	2
	8. Integrity of outer carbon steel WP barrier	4	5	1
Low rates of release for radionulides from breached waste packages	9. Integrity of corrosion-resistant WP barrier	3	6	3
	10. Seepage into waste package	3	3	0
	11. Integrity of spent fuel cladding	3	5	2
	12. Dissolution of spent fuel & glass waste forms	4	5	1
	13. Neptunium solubility	4	5	1
Concentration reduction transport from waste packages	14. Formation & transport of radionuclide-colloids	2	4	2
	15. Transport through and out of EBS	3	4	1
	16. Transport through unsaturated zone	2	5	3
	17. Flow and transport in saturated zone	2	3	1
	18. Dilution from pumping	5	5	0
	19. Biosphere transport and uptake	5	5	0

^A Emboldened factors discussed in detail. ^B The calculated priority for this factor has the same meaning as zero.

Principal Factors with Relatively High Priority

RSS Attributes	Principal Factors ^A	Current Conf.	Conf. Goal	Priority
Limited water contacting waste packages	1. Precipitation and infiltration into the mountain	4	5	1
	2. Percolation to depth	3	5	2
	3. Seepage into drifts	2	5	3
	4A. Effects of heat/excavation on flow (mountain)	1	2	1
	4B. Effects of heat/excavation on flow (drift scale)	2	4	2
	5. Dripping onto waste package	2	4	2
Long waste package lifetime	6. Humidity and temperature at waste package	5	4	0 ^B
	7. Chemistry of water on waste package	3	5	2
	8. Integrity of outer carbon steel WP barrier	4	5	1
Low rates of release for radionuclides from breached waste packages	9. Integrity of corrosion-resistant WP barrier	3	6	3
	10. Seepage into waste package	3	3	0
	11. Integrity of spent fuel cladding	3	5	2
	12. Dissolution of spent fuel & glass waste forms	4	5	1
	13. Neptunium solubility	4	5	1
Concentration reduction transport from waste packages	14. Formation & transport of radionuclide-	2	4	2
	15. Transport through and out of EBS	3	4	1
	16. Transport through unsaturated zone	2	5	3
	17. Flow and transport in saturated zone	2	3	1
	18. Dilution from pumping	5	5	0
	19. Biosphere transport and uptake	5	5	0

^A Emboldened factors discussed in detail. ^B The calculated priority for this factor has the same meaning as zero.

Technical Work Plans

- **Technical Work Identified based upon**
 - **Prioritization effort**
 - **Multi-year planning effort**
- **Technical work organized by functional areas**
 - **Site investigations**
 - **Design**
 - **Performance assessment**

Technical Work Plans

(Continued)

- **Examples of technical work**
 - **Natural analogs**
 - **Corrosion testing**

Technical Work

- **Insights from natural and man-made analogs**
 - **Fourth element of postclosure safety case**
 - **Confirmatory and supporting**
 - **Review and evaluation of existing relevant information**
 - **Studies continued during performance confirmation**

Technical Work

(Continued)

Natural Analogs addressed

- Site:**
- **Geologic framework and disruptive events**
 - **Unsaturated zone processes**
 - **Saturated zone processes**
 - **Near-field environment and coupled processes**
- Design:**
- **Waste package materials testing and modeling**
- Performance Assessment:**
- **Model abstractions**

Components of Analog Studies

Every analog study will include the following:

- Careful review of available data and understanding of analog system**
- Comparison of process or system to site-specific characteristics of a Yucca Mountain repository**
- Assessment of previous modeling studies and their application to Yucca Mountain processes**
- Qualitative or quantitative application of analog information in process and PA models for improved confidence in predicted Yucca Mountain behavior**

Uses of Natural Analogs for YMP

- **Confidence building in modeling processes for performance assessment**
- **Understanding long-term behavior of waste package and other engineered barrier materials, e.g. metals and cements**
- **Confidence in design – e.g., stability of old mines and other underground workings**
- **Public information and education**

FY99 and FY00 Analog Work

- **Comprehensive review of existing analog information relevant to performance of a Yucca Mountain repository with recommendations for process models and PA:**
 - seepage into drifts – Rainier Mesa, NV; Hell's Half Acre, ID
 - infiltration – Rainier Mesa
 - radionuclide solubility and speciation – Oklo, Gabon
 - radionuclide transport – Peña Blanca, Mexico; Cigar Lake, Canada
 - coupled processes – geothermal fields
 - colloidal transport – Nevada Test Site, INEEL
 - EBS materials - Maquarin, Jordan; Wairakai, New Zealand

FY99 and FY00 Analog Work

(Continued)

- **Scoping study of vertical uranium transport in unsaturated ash flow tuff at Peña Blanca, Mexico**
- **Modeling of fracture flow at INEEL and saturated zone dispersion at Hanford analog sites**
- **Study of coupled thermal-mechanical-hydrological-chemical process analogs at Krasnoyarsk, Russia and in geothermal fields worldwide**

Selected Natural Analog Sites



Technical Work

Corrosion

- **Relates to first and second elements of Postclosure Safety Case**
- **Illustrates prioritization of principal factors**
- **At least 6 of highest priority principal factors relate to corrosion:**
 - **Percolation to depth**
 - **Drift seepage**
 - **Dripping onto the waste package**
 - ***Chemistry of the water on waste packages***
 - ***Integrity of inner corrosion-resistant waste package barrier***
 - **Integrity of the spent nuclear fuel cladding**

Technical Work

(Continued)

Corrosion Addressed

Site: Geologic framework & disruptive events; unsaturated zone processes

Thermal testing

Near-field environment & coupled processes

Design: Surface - waste handling

Subsurface design: ventilation, ground control; waste emplacement

Waste package 3.2.2

3.2.2.9 waste package testing and modeling

PA: Model abstractions

Unsaturated zone flow & transport

Near-field environment

Waste package

Technical Work

(Continued)

- **Summary of status long-term corrosion studies**

Evolution in Priorities

- **Evolved from effort to develop the knowledge base for Yucca Mountain to confirming the knowledge base and reducing uncertainties in key areas**
- **Evolved from emphasis on scientific investigation to emphasis on design and performance assessment**

Evolution of Priorities

(Continued)

- **DOE has established higher confidence goals for the Engineered System in the License Application Plan than previously**
- **The goals for the Engineered System are as high or higher than goals for the natural system**
- **These goals provide higher priority on several aspects of the engineered system than in the past**
- **Ability to improve our understanding of the natural barriers is diminishing**
- **Our efforts are shifting from the natural system to the engineered system**

Confidence Goal Assessments

RSS Attributes	Principal Factors	* Signif. of Uncertainty	Current Conf.	Conf. Goal
Limited water contacting waste packages	1. Precipitation and infiltration into the mountain	M	4	5
	2. Percolation to depth	M	3	5
	3. Seepage into drifts	H	2	5
	4A. Effects of heat/excavation on flow (mountain)	M _b	1	2
	4B. Effects of heat/excavation on flow (drift scale)	M _b	2	4
	5. Dripping onto waste package	M	2	4
Long waste package lifetime	6. Humidity and temperature at waste package	L _{b,c}	5	4
	7. Chemistry of water on waste package	M	3	5
	8. Integrity of outer carbon steel WP barrier	M _a	4	5
Low rates of release for radionuclides from breached waste packages	9. Integrity of inner corrosion-resistant WP barrier	H _{a,b}	3	6
	10. Seepage into waste package	M	3	3
	11. Integrity of spent fuel cladding	H _a	3	5
	12. Dissolution of spent fuel & glass waste forms	M _{b,c}	4	5
	13. Neptunium solubility	M _{b,c}	4	5
Concentration reduction transport from waste packages	14. Formation & transport of radionuclide-colloids	M _{b,c}	2	4
	15. Transport through and out of EBS	M _{b,c}	3	4
	16. Transport through unsaturated zone	H _a	2	5
	17. Flow and transport in saturated zone	M	2	3
	18. Dilution from pumping	M	5	5
	19. Biosphere transport and uptake	L	5	5

* Subscripts: "a" = 0 to 10 kyr, "b" = 10 to 100 kyr, and "c" = 100 kyr to 1 Myr (no subscript = 0 to 1 Myr)

Funding

- **DOE has defined a program in the License Application Plan that we believe has fidelity and will lead to a docketable LA**
- **The License Application Plan established a funding program that will allow DOE to carry out that program**
- **Short falls in funding will cause slips in schedule**
- **Some work planned for 1999 has already been carried forward into 2000**