


Update on Scientific and Technical Investigations

Presentation to:
Nuclear Waste Technical Review Board (NWTRB)

Presentation by:
Dr. Mark T. Peters
Manager, Testing and Design Support Office
M&O/LANL

Alexandria, VA
September 14-15, 1999



U.S. Department of Energy
Office of Civilian Radioactive
Waste Management

Yucca
Mountain
Project

Overview



- **Climate; Infiltration; UZ Flow Above Repository; Seepage Into Drifts**
 - **Cross Drift Bulkhead Studies**
 - **ESF Moisture Monitoring**
 - » **Alcove 1**
 - » **Alcove 7**
 - **^{36}Cl Validation Study**
 - **Cooperative Work on Fluid Inclusions**

Overview

(Continued)

- **Coupled Processes - Effects on UZ Flow, UZ Transport, and Seepage; Environments on Drip Shield and Waste Package**
 - Drift Scale Test
- **UZ Flow and Transport - Advective Pathways and Colloid-Facilitated Transport; Radionuclide Retardation**
 - Busted Butte

Overview

(Continued)


- **SZ Flow and Transport - Advective Pathways and Colloid-Facilitated Transport; Radionuclide Retardation; Dilution of Radionuclide Concentrations**
 - **Saturated Zone Investigations**
 - » Integration of Nye County Results
 - » SD-6 Aquifer Pump Testing

Overview


(Continued)

- **Environments on Drip Shield and Waste Package; Performance of Drip Shield**
 - EBS Pilot-Scale Testing
- **Performance of Waste Package Barriers; Performance of Drip Shield; Environments within Waste Package**
 - Waste Package Materials Testing

Exploratory Studies Facility and Alcoves



Exploratory Studies Facility and Cross Drift




Cross Drift




- **Bulkhead Studies**
 - Evaluate flow and seepage processes in repository host rocks and Solitario Canyon Fault Zones
 - Began in mid June -- bulkheads at Stations 17+63 meters and 25+03 meters
 - Systematic hydrologic instrumentation in Topopah Spring Lower Lithophysal and Lower Nonlithophysal Units and Solitario Canyon Fault Zone
 - Entry approximately every two months for neutron logging, instrument maintenance, and TBM maintenance -- First entry September 1


Water Potentials in the ECRB



ECRB-XTRH08 - Station 25+25 m




XHDP19 - ECRB 22+25




ESF Moisture Monitoring


- **Alcove 1 -- Phase 2**
 - Evaluate infiltration and percolation through unsaturated welded tuffs and the climatic effects associated with increased precipitation
 - Water application started on 2/19/99
 - As of late August, approximately 41,700 gallons of water applied (varying application rates)
 - Water applied equals 7 years of average annual precipitation
 - Seepage in Alcove 1 began after approximately 3 weeks
 - As of late August, approximately 10% of the applied water was recovered in the alcove collection system
 - Varying concentration of aqueous tracer




Alcove 1 Infiltration Experiment



Applied Flux of Water (cm/day)



Alcove 1 Infiltration Experiment




ESF Moisture Monitoring

(Continued)

- **Alcove 7**
 - Evaluate flow and seepage processes associated with increased precipitation (1998 “El Nino” Event) in Ghost Dance Fault Zone
 - Isolated regions in the alcove within fault zone and adjacent areas using bulkheads
 - Rock returned to “ambient” conditions (i.e. > 99% relative humidity) relatively quickly
 - No dripping water has been detected either visually or using instrumentation

Water Potentials in Alcove 7 - 8/22/99



^{36}Cl Validation Study



- **Validate occurrence of “bomb-pulse” ^{36}Cl at two locations in the ESF -- Sundance Fault zone and Drillhole Wash Fault zone**
- **Collect core from boreholes at Sundance Fault zone and Drillhole Wash Fault zone**
- **Conduct Cl, ^{36}Cl , Tritium, U isotope, and ^{99}Tc analyses -- Study conducted by USGS, LLNL, LANL, AECL, and Purdue University**

^{36}Cl Validation Study

(Continued)

- **Status**

- **23 boreholes completed -- samples from 13 boreholes examined, split, and distributed; samples from 10 boreholes examined and split**
- **Procedures at USGS, LLNL, and AECL in place**
- **LLNL conducted test runs and ready to commence work on core; USGS extracted water from 10 core samples for tritium analyses; AECL has started U-series analyses**

Cooperative Work on Fluid Inclusions



- **Cooperative study involving UNLV, DOE (USGS), and State of Nevada to evaluate paleohydrology of Yucca Mountain**
- **Focus of sampling was in ESF and Cross Drift**
- **Technical Workshops held with all participants**
- **Current focus on selecting samples for more detailed study (petrography, geochemistry, and geochronology)**

Cooperative Work on Fluid Inclusions

(Continued)


- **Fluid inclusions indicating temperatures of 30-50°C observed in several samples and temperatures up to 80°C in two samples**
- **Microscopic observations by USGS suggest these fluid inclusions are restricted to the earliest (older) parts of the calcite/silica deposits -- probably within a few million years of deposition of the tuff**
- **Geochronologic measurements to be completed in FY00 are key dataset**

Drift Scale Test



- **Evaluate the thermal-hydrologic-mechanical-chemical coupled processes in repository horizon rocks at the field-scale**
 - **Heating phase continues**
 - » **Heat transfer is conduction-dominated with a key role played by moisture through convection**
 - » **Pore water mobilized by heat tending to move below the heated region rather than stay “ponded” above**
 - **As expected, coupled process phenomena occur at sub-boiling temperatures**


Drift Scale Test: As-Built Borehole Perspective



Drift Scale Test

(Continued)


Total Power and Drift-Wall Temperature



Drift Scale Test

(Continued)


Temperatures Parallel to the Wing Heaters Approximately at Mid-length of the Heated Drift (BH 160 and BH 164)



Drift Scale Test

(Continued)

Saturation Ratio Vs. Temperature





Busted Butte



- **Evaluate flow and transport processes and the effect of heterogeneities in unsaturated Calico Hills rocks**
- **Update on Phase 2**
 - **Tracer injection (tracers and microspheres) began June, 1998 and planned to continue into FY00**
 - **Continue to observe breakthrough on collection pads -- quantitative analyses ongoing**
 - **Introduced new tracer, which showed up almost immediately in geophysical logs**
 - » **Difference between ambient and system perturbed by ongoing injection**

Southern Busted Butte UZ Transport Test



Earth and Environmental Sciences


Los Alamos National Laboratory

Busted Butte

(Continued)

- **Applicability to Potential Repository Block**
 - **Busted Butte test bed primarily in a vitric subunit of Calico Hills**
 - » **Evaluating the role of fracture-matrix interaction, matrix diffusion, and matrix-dominated sorption for use in process model and TSPA**
 - **Calico Hills rocks exposed at Busted Butte are a distal extension of the formation located beneath the potential repository horizon - not an analog**
 - **Mineralogic-Petrologic Model provides framework for vitric/zeolitic distribution in Calico Hills rocks beneath potential repository block**


Stratigraphy: Comparison Between H-5 and Busted Butte



Busted Butte

(Continued)

Zeolite Abundance in the Calico Hills Formation
From the Integrated Site Model (ISM)



Saturated Zone Investigations

- **Integration of Nye County Data**
 - **DOE is incorporating data from the Nye County EWDP into the Site-Scale SZ Flow and Transport Model, including:**
 - **Lithologic data into the hydrogeologic framework model**
 - **Water-level data for flow field calibration**
 - **Hydraulic testing data for flow and transport model**
 - **Laboratory sorption measurements (^{237}Np , ^{129}I , and ^{99}Tc) on alluvium for process model and TSPA**
 - **Hydrochemistry data for flow field calibration**
 - **Eh/pH data for use in flow and transport model**
 - **DOE is establishing processes and interfaces for data transfer and control to allow for timely and quality incorporation of Nye County data**

Saturated Zone Investigations

(Continued)

- **SD-6 Aquifer Pump Testing**
 - **Evaluate SZ characteristics within the potential repository footprint**
 - **Preliminary Results**
 - » **Borehole was pumped for approximately two weeks at an average rate of 15.5 gpm**
 - » **Maximum drawdown was about 163 feet (majority within first day of pumping)**
 - » **No drawdown was observed in nearby boreholes**
 - » **Permeability of the water-bearing fractures is very low -- current hypothesis is secondary fractures were encountered and transmissivity estimates may not be representative of primary fracture system**

EBS Pilot-Scale Testing



- **Evaluate the performance of a Richard's Barrier in support of Design Alternative effort and potential backfill materials**
- **Test Canister #1 initiated in mid-December, 1998**
 - **EBS concept is Richard's Barrier (medium sand over coarse sand) under superpluvial rates**
 - **Richard's Barrier continues to effectively divert water (greater than 98% water diverted)**




Figure 1-1 cross-section view of ambient capillary barrier 1/4 scale

EBS - PILOT SCALE TESTING


CANISTER #1: RICHARDS BARRIER MATERIALS



A LAYER OF COARSE MATERIAL AND A LAYER OF FINE MATERIAL WAS HAND LOADED INTO CANISTER #1 CREATING A RICHARDS BARRIER FOR TESTING.




Water Balance






EBS Pilot-Scale Testing

(Continued)


- **Evaluate thermal-hydrologic processes in EBS containing drip shield and waste package**
- **Test Canister #3 initiated in early June, 1999**
 - **EBS concept is Drip Shield (fabricated from 2 cm thick 304 stainless steel) with crushed tuff invert (no backfill) at elevated temperatures**
 - **Phase 1 involves heating with no drip shield**
 - **Phase 2 involves heating with drip shield**
 - **Phase 3 involves heating with drip shield and dripping under superpluvial rates**





Engineered Barrier System

Canister 3 Temperatures



Waste Package Materials Testing



- **Objective is to confirm corrosion rates and mechanisms of candidate waste package and drip shield materials**
- **Both long-term and short-term testing is underway to address key materials degradation issues**
- **Test environments include range of expected water chemistries including near saturated J-13 solutions from dripping onto hot packages**

Waste Package Materials Testing

(Continued)

- **Localized corrosion testing is emphasizing cyclic polarization, crevice corrosion testing, and hydrogen pickup**
- **Long-term stability of passive films on Alloy 22, titanium Grade 7 and stainless steel is being evaluated utilizing short-term tests and detailed microstructural examination with the Atomic Force Microscope**

Waste Package Materials Testing

(Continued)

- **Stress corrosion cracking of all candidate alloys and hydrogen induced cracking of titanium alloys are being extensively evaluated utilizing a variety of crack initiation and growth tests**
- **Long-term thermal stability of Alloy 22 is being evaluated for the impact of the generation of ordered and precipitated intermetallic phases on long-term corrosion for both welded and aged specimens**