



U.S. Department of Energy  
Office of Civilian Radioactive Waste Management



# Waste Package Manufacturing and Closure Welds

Presented to:

**Nuclear Waste Technical Review Board**

Presented by:

**Jack D. Cloud**

**Manager Analyses and Component Design  
Bechtel SAIC Company, LLC**

**January 28, 2003**

**Las Vegas, Nevada**



# Waste Package Prototype Procurement

- **Determine population of qualified fabricators**
- **Constructed to exact requirements of actual production models**
- **Demonstration of fabrication process**
- **Integral part of design process**
- **First prototype coincident with License Application submittal**



# Waste Package Prototype Procurement

(Continued)

- **15 prototypes**
- **Uses of prototypes**
- **American Society of Mechanical Engineers (ASME) Code**
  - **Inner vessel**
  - **Corrosion barrier**
  - **Internals**
  - **ASME code position paper**



# Waste Package Prototype Schedule

(Calendar Years)

	2003	2004	2005	2006	2007	2008
WP Prototype #1	█	█	█			
WP Prototype #2		█	█	█		
WP Prototype #3		█	█	█		
WP Prototype #4		█	█	█		
WP Prototype #5			█	█	█	
WP Prototype #6			█	█	█	
WP Prototype #7			█	█	█	
WP Prototype #8			█	█	█	
WP Prototype #9				█	█	
WP Prototype #10				█	█	
WP Prototype #11				█	█	
WP Prototype #12				█	█	
WP Prototype #13					█	█
WP Prototype #14					█	█
WP Prototype #15					█	█




# Status of First Prototype Procurement

- **Fabrication specification and drawings**
- **ASME design specification**
- **Pre-qualification document**
- **Request for Proposal (RFP)**
- **Schedule**

• Pre-qualification	-- Feb 2003
• RFP	-- Mar 2003
• Bid Date	-- 3rd QTR 2003
• Award	-- 4th QTR 2003
• Deliver	-- 4th QTR 2004 - 1st QTR 2005 (Calendar years)



# Typical Waste Package



# Weld Process Verification

- **Recognize that there are various welding processes**
- **Weld selection process**
  - **Waste Package Closure Development Report**
- **Consultant position and conclusion**
  - **Dr. Carl Lundin - University of Tennessee**
  - **Confirmed Cold Wire - Gas Tungsten Arc Weld (CW-GTAW) welding process**




# Closure Welds at Yucca Mountain Project

- **Six-month value engineering study resulted in design modifications**
- **Recent design modifications**
- **Process equipment development and design strategy**
- **Contracting strategy**
- **Prototype strategy and schedule**
- **Prototypes are integral part of design**





# Waste Package Final Closure



**Site Recommendation Design**

**Proposed Design**



# Benefits of Design Modifications

- **Time in weld cell reduced by > 50%**
- **Eliminated thermal stress mitigation**
- **Less complicated fabrication and closure**
- **Reduced risk (licensing, operations, performance uncertainties)**
- **Cost savings**
- **Recommended by DOE Project Operations Review Board**



# Weld Process Equipment Contracting Strategy

- **Idaho National Engineering and Environmental Laboratory (INEEL)**
- **Commercial Contractor - Integrated with INEEL**
- **BSC Hire Specific Expertise**
- **Commercial Contractor**
  - **Future Generation Prototypes**
  - **Production Models - TBD**
- **Integral part of the Design Process**
- **5 Prototype Systems**



# Weld Process Equipment Contracting Strategy

(Continued)

- **Use of prototypes - installed in Training Facility**
  - Establish proof of concept and operations
  - Perform closure operations on waste package prototypes
  - Provide for operator training
  - Establish procedures and processes for Operations Readiness Review (ORR) and operations
  - Potentially used to perform ORR
  - Potentially used in operational facilities



# Weld Cell Process Equipment Development Schedule

(Calendar Years)

